NOTES:

1. THE POLE SHAFT SHALL BE 4 ½" O.D. x 0.237 WALL (SCHEDULE 40) 6063-T6 ALUMINUM, SPUN FINISH.
2. 4-INCH N.P.T. AT 8 THREADS/INCH.
3. FOR SQUARE BASE PEDESTAL SEE DETAIL 4825-3

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	ITS TYPE 'SB' POLE	DATE:	DETAIL NO.
STANDARD DETAIL		04/01/2009	4825-4