CCTV CAMERA
POLE MOUNTIING DETAIL

THE ROTATION OF THE CCTV CAMERA SHALL BE ALIGNED TO POINT AT THE TRAFFIC SIGNAL POLE ON THE DIAGONALLY OPPOSITE CORNER.

CCTV MOUNTING ASSEMBLY
ORIENTATION DETAIL

NOTES:

1. THE CONTRACTOR SHALL PROVIDE AND INSTALL A VIDEO ENCODER, AS SPECIFIED IN THE PLANS. ENCODER IS INSTALLED IN THE TRAFFIC SIGNAL CONTROL CABINET.
2. THE CCTV COMPOSITE CABLE SHALL RUN UNSPLICED FROM THE CCTV BACKBOX TO THE VIDEO ENCODER INSTALLED IN THE CONTROL CABINET.
3. INSTALLATION SHALL BE ACCORDING TO THE MANUFACTURE'S SPECIFICATIONS AND SHALL CARRY A MINIMUM FIVE-YEAR WARRANTY OF PARTS AND LABOR.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION STANDARD DETAIL	CCTV CAMERA INSTALLATION ON SIGNAL POLE	DATE: 10/10/2013	DETAIL NO. 4830