| MAST ARM INFORMATION | | | |
|---|---|---|---|
| Length | Ga. | 'D' Dim. | Tenon |
| 20' | 7 | 7" | 2 |
| 25' | 7 | 7" | 2 |
| 30' | 7 | 8" | 2 |
| 35' | 3 | 8 11/16" | 2 |
| 40' | 3 | 9 3/8" | 2 |

NOTES:

1. FOR CONSTRUCTION AND INSTALLATION SPECIFICATIONS SEE MCDOT SUPPLEMENT, SECTIONS 470 THRU 478.
2. THE POLE SHALL BE 3 GAUGE TAPERED STEEL.
3. USE 10' TENON SPACING FOR 20' MAST ARM.

| MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION | TYPE 'J' POLE | DATE: | DETAIL NO. |
|---|---|---|---|
| STANDARD DETAIL | | 10/1/2013 | 4742 |