NOTES:

1. FOR MATERIAL AND CONSTRUCTION SPECIFICATION SEE SECTION 472.
2. FOUNDATIONS SHALL HAVE A ⅝" x 10' BONDED COPPER GROUNDING ROD.
3. USE GROUT OR MASTIC TO SEAL GAP BETWEEN THE CABINET AND FOUNDATION.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	COMBINATION SERVICE PEDESTAL AND BATTERY BACKUP FOUNDATION	DATE:	DETAIL NO.
STANDARD DETAIL		01/01/2011	4724