ITEM	QTY.	DESCRIPTION
1	1	POLE PLATE (See Detail 4785)
2	4	BOLTS-½" x 20 x 1½"
3	1	1 1/2 " x 12" NIPPLE
4	2	1½" ELBOW (See Detail 4788)
5	2	1 ½" LOCK NIPPLE
6	1	NEOPRENE WASHER
7	1	WASHER, GALVANIZED
8	-	SIGNAL POLE SHAFT
9	1	¾" CHASE NIPPLE (INSULATING BUSHING)

SIDE MOUNT DETAIL

POLE DRILLING INFORMATION

ITEM	DIM.'A'
STANDARD SIGNAL	118"
PEDESTRIAN SIGNAL	87"

DIM. 'A' IS MEASURED FROM TOP OF POLE BASE TO CENTER OF BOTTOM POLE PLATE

NOTES:

1. SEE DETAIL 4773, FOR SIGNAL INDICATION COMBINATIONS.
2. SEE DETAIL 4785, FOR POLE PLATE DETAILS.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION STANDARD DETAIL	SIDE MOUNT (TYPE XI) ASSEMBLY (VEHICLE & PEDESTRIAN)	DATE: 4/09	DETAIL NO. 4775