ITEM	QTY.	DESCRIPTION
1	1	PULL BOX (SEE DETAIL 4711)
2	–	2" PVC ELECTRICAL CONDUIT, SCH. 40
3	–	SAW CUT FOR LOOP DETECTION SENSORS
4	–	LOOP SEALANT
5	–	LOOP DETECTION WIRES

SECTION A-A

NOTES:

1. FOR CONSTRUCTION AND INSTALLATION SPECIFICATIONS SEE MCDOT SUPPLEMENT, SECTIONS 470 THRU 478.
2. FILL LOOP SAWCUT FROM THE TOP OF CONDUIT STUB-OUT TO THE PAVEMENT SURFACE WITH LOOP SEALANT.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	CONDUIT STUB-OUT DETAIL WITHOUT CURB & GUTTER	DATE:	DETAIL NO.
STANDARD DETAIL		04/01/2009	4758