TYPE E PULL BOX

SECTION A-A

PLAN SYMBOL

NOTES:

1. PULL BOX SHALL BE OF PRECAST REINFORCED CONCRETE MATERIAL.
2. PULL BOX SHALL BE FURNISHED WITH HOOKS/RACKS AND UNISTRUT INSTALLED.
3. PULL BOX SHALL BE FURNISHED WITH A LOCKING LIP WITH SEAL BETWEEN WALL AND COVER ASSEMBLY.
4. TERMINATORS/ BELL ENDS SHALL ACCEPT 4-INCH AND 3-INCH DIA. CONDUIT SIZES.
6. UNISTRUT SHALL BE WIDE "C" CHANNEL (UNISTRUT P-3200 OR APPROVED EQUAL) AND SHALL BE EMBEDDED IN SIDEWALL A MINIMUM OF 6-INCHES FROM FINISHED FLOOR.
7. CABLE RACKS/ HOOKS MOUNTED IN UNISTRUT SHALL BE A MINIMUM OF 7-1/2 INCHES LONG.
8. FOR COVER ASSEMBLY, SEE DETAIL 4806-2.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION STANDARD DETAIL	ITS FIBER OPTIC PULL BOX TYPE E	DATE: 10/25/2013	DETAIL NO. 4806-1