NOTES:

1. FOR MATERIAL AND CONSTRUCTION SEE SECTIONS 471 AND 472.
2. ANCHOR BOLTS SHALL EXTEND 2" ABOVE THE FOUNDATION.
3. FOUR ¾" X 18" X 4" ANCHOR BOLTS. TOP THREADED LENGTH OF ANCHOR BOLTS SHALL BE MINIMUM OF 3". SEE DETAIL 4725
4. CONDUIT SHALL EXTEND A MINIMUM OF 3" AND A MAXIMUM OF 5" ABOVE THE TOP OF THE FOUNDATION.
5. INSTALL 25 FOOT COIL OF NO. 4 AWG BARE COPPER GROUNDING ELECTRODE 2 FEET ABOVE TOP OF FOUNDATION.
6. FOR CONDUIT SIZE, LOCATION AND QUANTITY, SEE PLANS.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	ITS SQUARE BASE ('SB') POLE FOUNDATION DETAIL	DATE:	DETAIL NO.
STANDARD DETAIL		04/01/2009	4825-2