DETAIL 'A'

NOTES:

1. FOR MATERIAL AND INSTALLATION SPECIFICATIONS SEE MCDOT SUPPLEMENT SECTIONS 470 THRU 478.
2. FOR CONDUIT SIZE, LOCATION, AND QUANTITY, SEE TRAFFIC SIGNAL PLAN.
3. FOR ANCHOR BOLT INFORMATION SEE MCDOT DETAIL 4725.
4. CONDUIT SHALL EXTEND A MINIMUM OF 2" AND A MAXIMUM OF 4" ABOVE THE TOP OF THE FOUNDATION EXCEPT THE CONDUIT FOR THE GROUND ROD, WHICH SHALL BE FLUSH WITH THE TOP OF THE FOUNDATION.
5. GROUT OR MASTIC SHALL BE USED TO SEAL GAP BETWEEN THE CABINET AND FOUNDATION.
6. IN UNPAVED AREAS A CABINET ACCESS PAD, 4"X36"X 48", SHALL BE PLACED IN FRONT OF CABINET AND FACED AWAY FROM INTERSECTION. PAD SHALL BE SET 2" BELOW THE FOUNDATION ELEVATION AND SLOPED AWAY FROM CABINET.
7. THE CABINET FOUNDATION SHALL HAVE A ⅝" X 8' BONDING COPPER ROD.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	'P' CABINET FOUNDATION	DATE:	DETAIL NO.
STANDARD DETAIL		05/01/2015	4723