ITEM	QTY.	DESCRIPTION
1	1	PULL BOX (SEE STD. DWG. 4711)
2	1	PVC ELECTRICAL CONDUIT, SCH. 40
3	1	PVC CAP
4	1	⅝" x 8' LONG GROUNDING ELECTRODE
5	1	1" SHORT GRADE ROCK

NOTES:

1. FOR MATERIAL AND CONSTRUCTION INSTALLATION SPECIFICATIONS SEE SECTION 471
2. BACKFILL WITH EXCAVATED MATERIAL AND COMPACT.
3. EXPANSION JOINT MATERIAL SHALL BE USED AROUND PULL BOX WHEN INSTALLED IN CONCRETE AREA.
4. WHEN INSTALLING PVC CONDUIT IT SHALL ENTER NEAR SIDES OF PULLBOX.
5. GROUNDING ELECTRODE.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION STANDARD DETAIL	TYPICAL TRAFFIC SIGNAL PULL BOX INSTALLATION	DATE: 1/1/2011	DETAIL NO. 4713