NOTES:

1. FOR MATERIAL AND CONSTRUCTION SPECIFICATIONS SEE SECTION 472.
2. FOUNDATIONS SHALL HAVE A ⅝" x 8' BONDED COPPER GROUND ROD.
3. USE GROUT OR MASTIC TO SEAL GAP BETWEEN SERVICE PEDESTAL AND FOUNDATION.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION STANDARD DETAIL	SERVICE PEDESTAL FOUNDATION	DATE: 1/1/2011	DETAIL NO. 4829-2