SECTION Y-Y

BASE PLATE DETAILS

SECTION X-X

NOTES:

1. FOR CONSTRUCTION AND INSTALLATION SPECIFICATIONS SEE MCDOT SUPPLEMENT, SECTIONS 470 THRU 478.
2. THE POLE SHALL BE A STANDARD 4" GALVANIZED PIPE, SCHEDULE 40, (0.237" WALL THICKNESS).
3. THE POLE PLATE SHALL BE ½" STEEL CONFORMING TO THE REQUIREMENTS OF ASTM A36.
4. A ¼" TAPPED HOLE FOR A GROUND CONNECTION SHALL BE PROVIDED.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	TYPE 'PB' POLE	DATE:	DETAIL NO.
STANDARD DETAIL		04/01/2009	4750