LEFT SIDE

FRONT VIEW

PLAN SYMBOL

BASE PLAN

NOTES:

1. FOR CONSTRUCTION SPECIFICATIONS SEE MCDOT SUPPLEMENT SECTIONS 470 THRU 478.
2. EXTERIOR SHALL BE 12 GA. H.D. GALVANIZED STEEL, THE INTERIOR SHALL BE 14 GA. COLD ROLLED STEEL. ALL WELDS SHALL BE ELECTRICALLY WELDED AND REINFORCED WHERE REQUIRED.
3. CONSTRUCTION SHALL BE NEMA 3R AND 12. RAINTIGHT AND DUSTTIGHT.
4. ALL NUTS, BOLTS, SCREWS AND HINGES SHALL BE STAINLESS STELL.
5. NUTS, BOLTS AND SCREWS SHALL NOT BE VISIBLE FROM OUTSIDE OF ENCLOSURE.
6. CONTROL WIRING SHALL BE MARKED AT BOTH ENDS WITH PERMANENT WIRE MARKERS.
7. A PLASTIC COVERED WIRING DIAGRAM SHALL BE SUPPLIED WITH ENCLOSURE.
8. THE ENCLOSURE SHALL BE FACTORY WIRED AND CONFORM TO REQUIRED NEMA STANDARDS.
9. FRONT OF CABINET ENCLOSURE SHALL FACE TOWARDS THE INTERSECTION.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	'SP' ELECTRICAL SERVICE PEDESTAL & 'BBS' BATTERY BACKUP SYSTEM CABINET	DATE:	DETAIL NO.
STANDARD DETAIL		04/01/2009	4731-1