NOTES:

1. FOR MATERIAL AND SPECIFICATIONS SEE MCDOT SUPPLEMENT, SECTIONS 470 THRU 478
2. INSTALL 3" DIA. PVC CONDUIT BETWEEN TYPE "E", "F", "J", "Q", "K" or "R" POLE FOUNDATION LOCATIONS AND NO. 7 SIGNAL PULL BOXES. (TYP).
3. INSTALL 2-3" DIA. PVC CONDUIT BETWEEN CONTROL CABINET AND NO. 7 SIGNAL PULL BOX WITH EXTENTION.
4. INSTALL 3" DIA. PVC CONDUIT BETWEEN TELEPHONE SERVICE PEDESTAL AND CONTROLLER CABINET.
5. INSTALL 2" DIA. PVC CONDUIT BETWEEN SERVICE PEDESTAL/ BATTERY BACK-UP CABINET FOUNDATION AND CONTROLLER CABINET FOUNDATION. MINIMUM SPACING SHALL BE 10'.
6. INSTALL 2½" OR 3" DIA. PVC CONDUIT BETWEEN POINT OF SERVICE SERVICE PEDESTAL/BATTERY BACK-UP FOUNDATIONS REQUIRED BY THE ELECTRICAL SERVICE COMPANY.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION STANDARD DETAIL	TYPICAL TRAFFIC SIGNAL PULL BOX AND CONDUIT RUN LAYOUT	DATE: 9/27/2013	DETAIL NO. 4716