MAST ARM INFORMATION			
Length	Gauge	'D'Dim.	Tenon
45'	0 & 3	10 1/16"	3
50'	0 & 3	10 3/4"	3
55'	0 & 3	11 7/16"	3

*** FIRST 25' OF THE 50' & 55' MAST ARM AND THE FIRST 20' OF THE 45' MAST ARM SHALL BE 0 GAUGE. THE REMAINDER OF THE MAST ARMS SHALL BE 3 GAUGE.

NOTES:

1. FOR CONSTRUCTION AND INSTALLATION SPECIFICATIONS SEE MCDOT SUPPLEMENT, SECTIONS 470 THRU 478.
2. THE POLE SHALL BE 0 GAUGE TAPERED STEEL.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	TYPE 'K' POLE	DATE:	DETAIL NO.
STANDARD DETAIL		04/01/2009	4748