NOTES

1. MAILBOX SUPPORT POST SHALL BE A 4"X4" S4S REDWOOD POST NO. 2, PENA-TREATED SOUTHERN PINE, OR EQUIVALENT. ALTERNATIVE MAILBOX SUPPORTS ARE SUBJECT TO MCDOT APPROVAL.

2. ROADWAY SHOULDER TO HAVE A MINIMUM OF 4 INCH DEPTH OF ABC FOR THE FULL SHOULDER WIDTH TO ALLOW ALL WEATHER ACCESS.

3. MULTIPLE INSTALLATION OF SINGLE MAILBOXES ALONG UNCURBED ROADWAYS SHALL BE SPACED AT 4' (MINIMUM) ON CENTER.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	MAILBOX INSTALLATION	DATE:	DETAIL NO.
STANDARD DETAIL		09/26/2017	2066