STEEL POST DETAIL

WOOD POST DETAIL

NOTE:

The concrete leave out area for CLSM may be rectangular or circular in shape. The rectangular area is as dimensioned.

For steel posts the circular leave out area shall have a radius of eight inches (8”) located 16¾” back of the rail face and centered on the post.

For wood posts with an 8” block out the circular leave out area shall have a radius of nine inches (9”) located 19¼” back of the rail face and centered on the post. For wood posts with a 12” block out the circular leave out area shall have a radius of nine inches (9”) located 23¼” back of the rail face and centered on the post.

SECTION A-A

SECTION B-B

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION STANDARD DETAIL	GUARDRAIL POST INSTALLATION FOR CONCRETE PAVED AREAS	DATE: 11/14	DETAIL NO. 3004