| ITEM | QTY. | DESCRIPTION |
|---|---|---|
| 1 | 1 | PULL BOX (SEE DETAIL 4711) |
| 2 | – | 2" PVC ELECTRICAL CONDUIT, SCH. 40 |
| 3 | – | CURB & GUTTER |
| 4 | – | SAW CUT FOR LOOP DETECTION SENSORS |
| 5 | – | LOOP SEALANT |
| 6 | – | LOOP DETECTION WIRES (SEE NOTE 4) |

SECTION A-A

NOTES:

1. FOR CONSTRUCTION AND INSTALLATION SPECIFICATIONS SEE MCDOT SUPPLEMENT, SECTIONS 470 THRU 478.
2. CHISEL 'X' MARK ON LIP OF GUTTER TO MARK END OF CONDUIT LOCATION.
3. END OF PVC TO BE CUT FLUSH WITH GUTTER.
4. COIL 2' MIN. OF LOOP WIRE IN PULL BOX.
5. FILL LOOP SAWCUT FROM THE TOP OF CONDUIT STUB-OUT TO THE PAVEMENT SURFACE WITH LOOP SEALANT.

| MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION | CONDUIT STUB-OUT DETAIL WITH CURB & GUTTER | DATE: | DETAIL NO. |
|---|---|---|---|
| STANDARD DETAIL | | 04/01/2009 | 4759 |