MAST ARM INFORMATION					
Length	Rise	Ga.	"D"Min.	Ga.	"D"Min.
12'	4'-3"	11	4 15/16"	10	4 5/16"
15'	4'-9"	11	5 5/16"	10	4 3/4"
18'	5'-9"	11	5 13/16"	10	5 3/16"
20'	5'-9"	7	5 1/4"	7	5 1/4"

NOTES:

1. FOR CONSTRUCTION AND INSTALLATION SPECIFICATIONS SEE MCDOT SUPPLEMENT, SECTIONS 470 THRU 478.
2. THE POLE SHALL BE 7 GAUGE TAPERED STEEL.

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	TYPE 'E' POLE	DATE:	DETAIL NO.
STANDARD DETAIL		10/25/2013	4740