PLAN

ELEVATION

GENERAL NOTES:

1. OMIT AS FEW POSTS AS NEEDED TO SPAN FEATURES WITH LESS THAN 48" OF COVER. A MAXIMUM OF 3 POSTS MAY BE OMITTED.
2. THREE CONTROLLED RELEASING TERMINAL (CRT) POSTS ARE REQUIRED ON EACH SIDE OF THE OMITTED POSTS. CRT POSTS ARE NOT REQUIRED IF ONLY ONE POST IS OMITTED.
3. UNLESS OTHERWISE SHOWN ON PLANS, INSTALL A MINIMUM OF 50' OF GUARDRAIL BEYOND THE FIRST CRT POST OR STANDARD POST ON EITHER SIDE OF THE MISSING POST(S); EXCLUSIVE OF TRANSITIONS, TAPERS, END ANCHORS, END TERMINALS, OR OTHER LONG-SPAN INSTALLATIONS.

SYMBOLS

- INDICATES W BEAM SPLICE CONNECTION.

- 72" CRT POST (SEE DETAIL 3100)

MARICOPA COUNTY DEPARTMENT OF TRANSPORTATION	MIDWEST GUARDRAIL SYSTEM (MGS) LONG-SPAN CULVERT APPLICATIONS	DATE:	DETAIL NO.
STANDARD DETAIL		01/01/2019	3108